



Clark County Department of Building & Fire Prevention

Building Division – Inspection Services

Field Inspection Guideline

SUBJECT: Fiberglass Pools Pre-Plaster Inspection	FIG-B-003	
<i>Effective Date:</i> July 10, 2005	<i>Revised:</i> June 17, 2014	<i>Approved By:</i> BAT
<i>Code Chapter:</i> 2012 ISPSC Section 305		Page 1 of 1

Interpretation: Temporary fencing may be used to meet the pool fence barrier requirements during construction.

Field Application: The first inspection on a fiber glass pool installation with an ES report may be approved without the permanent barrier in place. The temporary barrier will be noted in the inspection history and the comment section of the job site inspection history card.

The perimeter barrier may have a temporary fencing for the purpose of getting sand and equipment into the backyard and for backfilling around the pool shell. Permanent fencing shall be in place at the time of the pool pre-deck inspection.

The temporary closure barrier shall meet the Code requirement of 5 feet in height with no openings greater than 4 inches, or chain link fencing 5 feet in height with a mesh maximum opening of 1 ¼ inches. The temporary barrier shall be securely held in place until the permanent barrier is installed and inspected with the pre-deck inspection. The approval of the permanent barrier shall be noted in the inspection history.

Revision History:

Reference #	Title	Effective Date	Revised	Reviewed
FIG-B-003	Fiberglass Pools Pre-Plaster Inspection	July 10, 2005	June 06, 2013	
FIG-B-003	Fiberglass Pools Pre-Plaster Inspection		June 17, 2014	