

TASK ANALYSIS
AEC III (M2, M3, M5, M7, M8)

November 1, 2004
TG-17-2004-IBC, Appendix E-3

MODULES (M)	Module Tasks & Representative Subtasks	Percent of All Tasks
MODULE 2: Typical Laboratory tests of soils		15%
TASK M 2.1	- USCS Classification System (ASTM ASTM D 2487)	
Subtasks:	1 Understand the test	
	2 Perform the test	
	3 Understand factors that may affect test results	
TASK M 2.2	- Visual Identification of soils (ASTM D 2488)	
Subtasks:	1 Understand the test	
	2 Perform the test	
	3 Understand factors that may affect test results	
MODULE 3: Advanced Laboratory Tests of Soils		4%
TASK M 3.1	- Consolidation Test (ASTM D 2435)	
Subtasks:	1 Understand test results	
TASK M 3.2	- Percent Water-Soluble Sulfates Test (AWWA 4500-E)	
Subtasks:	1 Understand test results	
TASK M 3.3	- Expansion Potential Tests (ASTM D 3877) & Swell Test (SNBCA 1803.2)	
Subtasks:	1 Understand test results	
TASK M 3.4	- Solubility Tests (AWWA 2540)	
Subtasks:	1 Understand test results	
MODULE 5: Grading plans & construction staking		20%
TASK M 5.1	- Grading Plans	
Subtasks:	1 Identification of natural, existing, and design contours	
	2 Identification of Cut/fill line	
	3 Identification of cut/fill transition	
	4 Identification of cut areas	
	5 Identification of fill areas	
	6 Identification of extent of grading within the Permit Area	
	7 Understand grading plan details	
	8 Understand topography depicted on grading plans	
	9 Identification of project occurrences on grading plans (overexcavation limits, stockpiles, etc.)	
	10 Identification of project occurrences on grading plans (fill keys, transition lots, rock fills, etc.)	

TASK ANALYSIS
AEC III (M2, M3, M5, M7, M8)

November 1, 2004
TG-17-2004-IBC, Appendix E-3

MODULES (M)	Module Tasks & Representative Subtasks		Percent of All Tasks
TASK M 5.2	-	Construction Staking	
Subtasks:	1	Understand the use of construction or surveys stakes	
	2	Identify various markings used on construction or survey stakes	
MODULE 7: Basics of grading operations of low-risk projects, i.e., grading projects with no adverse soil conditions			27%
TASK M 7.1	-	Implementation of Laboratory test results during grading operations	
Subtasks:	1	Implementation of sieve analysis test results	
	2	Implementation of MDD-OMC test results	
	3	Implementation of Atterberg limits test results	
	4	Implementation of expansion test results	
	4	Implementation of solubility test results	
TASK M 7.2	-	Shallow Foundations, Retaining Walls, Geosynthetics-reinforced soils	
Subtasks:	1	Identify foundation details	
TASK M 7.3	-	Earthwork Construction	
Subtasks:	1	Be familiar with general soil conditions in the Las Vegas Valley and the standard practice dealing with typical soil conditions	
	2	Identify competent soil for cleanouts or overexcavation	
	3	Identify competent soil or bedrock for cleanouts, or overexcavation	
MODULE 8: basics of grading operations of high-risk projects, i.e., grading projects with adverse soil conditions including hillside grading			34%
TASK M 8.1	-	Geotechnical Reports	
Subtasks:	1	Understand boring logs	
	2	understand site geology	
	3	Understand project soils conditions	
	4	Understand report's earthwork construction recommendations (overexcavation, fill material, compaction, etc.)	
TASK M 8.2	-	Adverse Soil Conditions (Expansive, hydrocollapsible, soluble or salt-laden soils, soil-rock and rock fills)	
Subtasks:	1	Identify above soil conditions	
	2	Understand the various tests) that may assist in field identification of above soil conditions	
	3	Verify that approved recommendations addressing above soil conditions are implemented	
	4	Verify by observation and/or testing proper placement and compaction of above soil conditions	

TASK ANALYSIS
AEC III (M2, M3, M5, M7, M8)

November 1, 2004
TG-17-2004-IBC, Appendix E-3

MODULES (M)	Module Tasks & Representative Subtasks		Percent of All Tasks
TASK M 8.3 - Adverse Soil Conditions: Mechanically-stabilized soils (Geosynthetics) and Chemically stabilized soils (lime, cement, others)			
Subtasks:	1	Understand the criteria used in differentiating the above soil conditions	
	2	Identify from the geotechnical report or existing field conditions the presence of any of the above soils conditions	
	3	Understand the various tests) that may assist in field identification of above soil conditions	
TASK M 8.4 - Adverse Soil Conditions (Hillside Grading)			
Subtasks:	1	Understand the criteria used in identifying hillside grading	
	2	Identify competent soil or bedrock for cleanouts, or overexcavation, or benching	
	3	Understand the need for fill keys	
	4	Understand the impact of site geology and topography on hillside grading	
	5	Understand the geotechnical report's earthwork construction recommendations related to hillside grading	
	6	Understand Clark County Codes related to hillside grading (SNBCA, UBC, etc.)	
TASK M 8.5 - Geology			
Subtasks:	1	Regional setting	
	2	Regional geology	
	3	Regional hydrogeology	
	4	Alluvial soils of the Las Vegas Valley	
	5	Compaction faults	
	6	Fissures	
Number of Tasks is			Total AEC III
16			100%